

SECTION 310000**EARTHWORK**

NOTE: HIDDEN TEXT IS INCLUDED WITHIN THIS SPEC TO ASSIST IN THE EDITING OF THIS DOCUMENT. ONCE EDIT IS COMPLETE, DELETE ALL HIDDEN TEXT SO THAT IT DOES NOT APPEAR IN THE FINAL DOCUMENT. BE SURE TO DELETE THIS PARAGRAPH.

PART 1 GENERAL**1.01 RELATED WORK SPECIFIED ELSEWHERE**

- A. Site Restoration: Section 310101.
- B. Rock Removal: Section 312316.
- C. Topsoil: Section 329120.
- D. Seeding: Section 329219.

1.02 DEFINITIONS

- A. The following terms have the meanings ascribed to them in this Article, wherever they appear in this Section.
 - 1. Earth Excavation: The removal of all surface and subsurface material not classified as rock as defined below.
 - 2. Rock: Limestone, sandstone, shale, granite, and similar material in solid beds or masses in its original or stratified position which can be removed only by blasting operations, drilling, wedging, or use of pneumatic tools, and boulders with a volume greater than 1.0 cu yd. Concrete building foundations and concrete slabs, not indicated, with a volume greater than 1.0 cu yd shall be classified as rock.
 - a. Limestone, sandstone, shale, granite, and similar material in a broken or weathered condition which can be removed with an excavator or backhoe equipped with a bucket with ripping teeth or any other style bucket shall be classified as earth excavation.
 - b. Masonry building foundations, whether indicated or not, shall be classified as earth excavation.
 - 3. Unclassified Earth Excavation: The excavation and disposal of all surface and subsurface materials of any description necessary to perform the work of this contract. This will include:
 - a. All soil deposits of any description both above and below groundwater levels. These may be naturally deposited or placed by previous construction operations.
 - b. Ledge rock of all quality. (Limestone, Sandstone, Shale, Granite and similar materials in solid beds or masses in its original or stratified position which can only be removed by drilling, wedging, use of pneumatic tools or heavy ripping equipment.) Blasting operations will not be permitted to loosen any ledge rock necessary to be removed in this contract.
 - c. Boulders of any size.

- d. Any materials of man-made origin.
4. Subgrade Surface: Surface upon which subbase or topsoil is placed.
5. Subbase: Select granular material or subbase course Type 2 which is placed immediately beneath pavement or concrete slabs.
6. Foundation Bearing Grade: Grade/elevation at which the bottom-of-footings are constructed.
7. Maximum Density: The dry unit weight in pounds per cubic foot of the soil at "Optimum Moisture Content" when determined by ASTM D 698 (Standard Proctor), or ASTM D 1557 (Modified Proctor).
8. Structures: Buildings, footings, foundations, retaining walls, slabs, tanks, mechanical and electrical appurtenances, or other man-made stationary features constructed above or below the ground surface.
9. Landscaped Areas: Areas not covered by structures, walks, roads, paving, or parking.
10. Unauthorized Excavation: The removal of material below required elevation indicated on the Drawings or beyond lateral dimensions indicated or specified without specific written direction by the Director's Representative.
11. Grading Limit Line (Shown on Drawings): Limits of grading, excavations and filling required for the work of this contract. Unless specifically noted otherwise, the Grading Limit Line and Contract Limit Line will be considered the same.

1.03 SUBMITTALS

- A. Shop Drawings:
 1. Sheeting, Shoring, and Bracing (Shown on the Drawings): Submit shop drawings for sheeting, shoring, and bracing shown on the Drawings. Shop drawings will be signed by a New York State licensed Professional Engineer.
- B. Product Data:
 1. Permanent Sheeting, Shoring, and Bracing: Specifications for materials and accessories.
 2. Filter Fabric: Manufacturer's catalog sheets, specifications, and installation instructions.
 3. Geogrid: Manufacturer's catalog sheets, specifications, and installation instructions.
- C. Samples: Submit samples as follows. Take the samples in the presence of the Director's Representative, and submit to the Director's Representative the laboratory test results for gradation, proctors and soundness tests, when required. These tests will be performed in accordance with ASTM standards, will be performed and signed by a certified soils laboratory, and will be submitted as part of the original submittal. At a minimum the samples taken will be of the following quantities:
 1. Select Granular Material: 50 - 60 lb. (Two Samples).
 2. Subbase Course Type 2: 50 - 60 lb. (Two Samples).
 3. Selected Fill: 40 - 50 lb.
 4. Cushion Material: 30 lb.

5. Item B-12: 30lb, each gradation.
6. Crushed Stone: 30 lb.
7. Underdrain Filter Material: 40 - 50 lb.
8. Crushed Stone, Crushed Gravel, or Screened Gravel (Wastewater): 30 lb., each layer gradation (if more than one).
9. Sand Filter Material (Wastewater): 30 lb.

D. Quality Control Submittals:

1. Subbase Materials: Name and location of source and the DOT Source Number. If the material is not being taken from an approved DOT Source the results of the gradation and soundness tests performed by an ASTM certified soils laboratory will be required.
2. Other Aggregates: Name and location of source and soil laboratory test results.
3. Excavation Procedure: Submit a lay out drawing or detailed outline of intended excavation procedure for the Director's information. This submittal will not relieve the Contractor of responsibility for the successful performance of intended excavation methods.
4. Sheet piling, Shoring, and Bracing (Not shown on the Drawings): Submit a detailed plan of intended sheet piling, shoring and bracing, signed by a New York State licensed Professional Engineer, for the Director's information. This submittal will not relieve the Contractor of responsibility for the successful performance of the intended sheet piling, shoring and bracing methods.

1.04 DELIVERY, STORAGE, AND HANDLING

- A. Protect filter fabric from sunlight during transportation and storage.

1.05 PROJECT CONDITIONS

- A. Protect existing trees and plants during performance of the Work unless otherwise indicated. Box trees and plants indicated to remain within the grading limit line with temporary steel fencing or solidly constructed wood barricades as required. Protect root systems from smothering. Do not store excavated material, or allow vehicular traffic or parking within the branch drip line. Restrict foot traffic to prevent excessive compaction of soil over root systems.
- B. Cold Weather Requirements:
1. Excavation: When freezing temperatures are anticipated, do not excavate to final required elevations for concrete work unless concrete can be placed immediately.
 2. Backfilling: If backfill is being placed during freezing temperatures the backfilling operations will be monitored by the Director's Representative and the following procedures will be followed:
 - a. Frozen ground will be removed in its entirety from beneath and five feet beyond the area of fill placement.
 - b. The fill material placed will consist of Selected Fill and will be free of all frozen chunks that exceed four inches in size. The

material transported to the project site will only consist of material excavated from below the frost depth.

- c. At the end of the work day, the area of fill placement will be covered with insulated blankets, or left unprotected. Other means of protection (hay, wood chips, etc.) may also be used for protection provided it is approved by the Director's Representative.
 - d. Following work day - Remove the insulated blankets and/or strip the area of all frozen material as specified previously.
 - e. Upon establishing the subgrade elevations, protect the grades with insulated blankets or place additional material that will adequately insulate the exposed earth surface from frost. This additional fill or protective material will be stripped just prior to pouring concrete.
- C. Thru-traffic or fill placement with heavy construction vehicles or equipment which causes rutting or weaving to occur within the perimeter of a building will not be permitted. If rutting or weaving occurs during placement of fill, place specified fill in a stable area outside building perimeter and spread with tracked equipment to specified layer thickness.

PART 2 PRODUCTS

2.01 MATERIALS

- A. Select Granular Material: Stockpiled, sound, durable, sand, gravel, stone, or blends of these materials, free from organic and other deleterious materials. Comply with the gradation and material requirements specified below:

Sieve		Percent Passing
Sieve Size	Size opening (mm)	
2 inch	50.8	100
1/4 inch	6.35	30-65
No. 40	0.425	5-40
No. 200	0.075	0-10

- 1. Magnesium Sulfate Soundness Test: 20 percent maximum loss by weight after four test cycles.
 - 2. Plasticity Index: The plasticity index of the material passing the No. 40 mesh sieve will not exceed 5.0.
 - 3. Elongated Particles: Not more than 30 percent, by weight, of the particles retained on a 1/2 inch sieve will consist of flat or elongated particles. A flat or elongated particle is defined as one which has its greatest dimension more than three times its least dimension.
- B. Subbase Course Type 2: Stockpiled, crushed ledge rock or approved blast furnace slag. Comply with the gradation and material requirements specified below:

Sieve		Percent Passing
Sieve Size	Size opening (mm)	
2 inch	50.8	100
1/4 inch	6.35	25-60
No. 40	0.425	5-40
No. 200	0.075	0-10

1. Magnesium Sulfate Soundness Test: 20 percent maximum loss by weight after four test cycles.
 2. Plasticity Index: The plasticity index of the material passing the No. 40 mesh sieve will not exceed 5.0.
 3. Elongated Particles: Not more than 30 percent, by weight, of the particles retained on a 1/2 inch sieve will consist of flat or elongated particles. A flat or elongated particle is defined as one which has its greatest dimension more than three times its least dimension.
- C. Selected Fill: Sound, durable, sand, gravel, stone, or blends of these materials, free from organic and other deleterious materials. Comply with the gradation requirements specified below:

Sieve		Percent Passing
Sieve Size	Size opening (mm)	
4 inch	101.6	100
No. 40	0.425	0-70
No. 200	0.075	0-15

- D. Suitable Material (Fill and Backfill for Landscaped Areas): Material consisting of mineral soil (inorganic), blasted or broken rock and similar materials of natural or man-made origin, including mixtures thereof. Maximum particle size will not exceed 2/3 of the specified layer thickness prior to compaction. NOTE: Material containing cinders, industrial waste, sludge, building rubble, land fill, muck, and peat will be considered unsuitable for fill and backfill, except topsoil and organic silt may be used as suitable material in landscaped areas provided it is placed in the top layer of the subgrade surface.
- E. Cushion Material: Will consist of clean, hard, durable, uncoated particles, free from lumps of clay and all deleterious substances and will meet the following gradation requirements:

Sieve Size		Percent Passing
Sieve Size	Size opening (mm)	
1/4 inch	6.35	100
No. 60	0.25	0-35
No. 100	0.15	0-10

- F. Item B-12: Equal Blend of No.1 and No. 2 Crushed Stone that complies with material requirements of DOT Article 703-02, crushed stone only.

Sieve	Percent Passing
-------	-----------------

Sieve Size	Size opening (mm)	
1-1/2 inch	38.1	100
1 inch	25.4	95-100
1/2 inch	12.7	45-60
1/4 inch	6.35	0-15

- G. No. 1 Coarse Aggregate: Crushed Stone that complies with material requirements of DOT Article 703-02 and meets the following gradation.

Sieve		Percent Passing
Sieve Size	Size opening (mm)	
1 inch	25.4	100
1/2 inch	12.7	90-100
1/4 inch	6.35	0-15

- H. No. 2 Coarse Aggregate: Crushed Stone that complies with material requirements of DOT Article 703-02 and meets the following gradation.

Sieve		Percent Passing
Sieve Size	Size opening (mm)	
1-1/2 inch	38.1	100
1 inch	25.4	90-100
1/2 inch	12.7	0-15

- I. Rip Rap: Fine, Light, Medium or Heavy Stone Filling that complies with DOT Article 620-2.02 for stone filling.

- J. Pea Gravel: Comply with DOT Article 703-02 for screened gravel.

Sieve		Percent Passing
Sieve Size	Size opening (mm)	
1/2 inch	12.7	100
1/4 inch	6.35	90-100
1/8 inch	3.17	0-15
No. 200 Sieve	0.075	0-1

- K. Flowable Fill: Shall consist of a mixture of Portland cement, sand, water and admixtures proportioned to provide a non-segregating, free-flowing, self-consolidating material that will result in a hardened, dense backfill.

1. Shall have a 28 day compressive strength between 40 and 100 psi.

2.02 GEOTECHNICAL FABRICS

- A. Filter Fabric (GeoTextile):

1. Drainage and Erosion Control: Amoco 1199 & 2019, Maccaferri MacTex MX140 & MX155, Mirafi 140N & 160N, Fiberweave 403 & 404 or equivalent.

2. Separation for foundation drains, underdrains, undercuts: Amoco 2002 & 2004, Contech Construction Products Inc. C-180, Synthetic Industries Geotex 250ST & 315ST, Mirafi Geolon HP570 & HP1500 or equivalent.
3. Separation/Stabilization beneath pavements: GeoTex 801, Bonded Fibers Products PN080, Maccaferri Gabions MacTex MX275 & 340, Mirafi 160N & 180N or equivalent.

B. Geogrids:

1. Segmental Retaining Walls.
2. Subgrade Stabilization.

2.03 WASTEWATER MATERIAL

A. Crushed Stone, Crushed Gravel, or Screened Gravel (Wastewater): Comply with applicable portions of DOT Section 703-02, except as otherwise indicated.

1. Gradation: No. 6 Sieve to 1/4 inch and 3/4 to 1-1/2 inches.
2. Gradation:
 - a. Top Layer: No. 6 Sieve to 1/4 inch.
 - b. Middle Layer: 1/4 to 3/4 inch.
 - c. Bottom Layer: 3/4 to 1-1/2 inches.
3. Gradation: 3/4 to 1-1/2 inches.
4. Gradation: 1-1/2 to 2-1/2 inches.

B. Sand Filter Material (Wastewater): Silica sand or other sound sand free from clay, loam, soft limestone or other impurities which may be disintegrated by sewage liquid.

1. Organic Content: Less than 1 percent; ASTM D2974 method and calculation.
2. Uniformity Coefficient: 4.0 or less.
3. Calcium Carbonate Content: Less than 3 percent by ASTM D4373.
4. Magnesium Sulfate Soundness Test: Less than 10 percent loss by weight after 5 test cycles by ASTM C88.
5. Shape: Rounded or oval. Do not use sharp sand, crushed flint or gravel.
6. Effective Size: 0.50 to 1.0 mm.
7. Effective Size: 0.25 to 1.0 mm.
8. Effective Size: 0.50 to 1.0 mm.
9. Effective Size: 0.25 to 1.0 mm.

2.04 SHEETING, SHORING, AND BRACING

A. Steel Sheetpiling: Continuous interlock type complete with all required accessories, complying with ASTM A 328 or ASTM A 572.

1. Furnish steel sheetpiling of design, configuration, and length to resist pressure of earth to be retained.

PART 3 EXECUTION

3.01 CLEARING AND GRUBBING

- A. Clear and grub the Site within the Grading Limit Line (GLL) of trees, shrubs, brush, other prominent vegetation, debris, and obstructions except for those items indicated to remain. Completely remove stumps and roots protruding through the ground surface.
 - 1. Use only hand methods for grubbing inside the drip line of trees indicated to be left standing.
 - 2. Where roots and branches of trees indicated to be saved interfere with new construction, carefully and cleanly cut them back to point of branching.
- B. Fill depressions caused by the clearing and grubbing operations in accordance with the requirements for filling and backfilling, unless further excavation is indicated.

3.02 REMOVAL OF TOPSOIL

- A. Remove existing topsoil from areas within the Grading Limit Line where excavation or fill is required.
- B. Stockpile approved topsoil where directed until required for use. Place, grade, and shape stockpiles for proper drainage.
 - 1. Topsoil will be tested prior to stockpiling. Stockpile only quantities of topsoil approved in writing for re-use.

3.03 UNDERGROUND UTILITIES

- A. Locate existing underground utilities prior to commencing excavation work. Determine exact utility locations by hand excavated test pits. Support and protect utilities to remain in place.
- B. Do not interrupt existing utilities that are in service until temporary or new utilities are installed and operational.
- C. Utilities to remain in service: Will be re-routed as shown on the Contract Drawings.
- D. Utilities abandoned beneath and five feet laterally beyond the structure's proposed footprint will be removed in their entirety. Excavations required for their removal will be backfilled and compacted as specified herein.
- E. Utilities extending outside the five feet limit specified above may be abandoned in place provided their ends are adequately plugged as described below.
 - 1. Permanently close open ends of abandoned underground utilities exposed by excavations, which extend outside the limits of the area to be excavated.
 - 2. Close open ends of metallic conduit and pipe with threaded galvanized metal caps or plastic plugs or other approved method for the type of material and size of pipe. Do not use wood plugs.
 - 3. Close open ends of concrete and masonry utilities with concrete or flow-able fill.

3.04 EXCAVATION

- A. Excavate earth as required for the Work.
- B. Install and maintain all erosion and sedimentation controls during all earthwork operations as specified on the Contract Drawings or as directed by local officials. If the erosion and sedimentation controls specified by the local officials are more stringent than those specified on the Contract Drawings contact the Director's Representative.
- C. Maintain sides and slopes of excavations in a safe condition until completion of backfilling. Comply with Code of Federal Regulations Title 29 - Labor, Part 1926 (OSHA).
 - 1. Trenches: Deposit excavated material on one side of trench only. Trim banks of excavated material to prevent cave-ins and prevent material from falling or sliding into trench. Keep a clear footway between excavated material and trench edge. Maintain areas to allow free drainage of surface water.
- D. Stockpile excavated materials classified as suitable material where directed, until required for fill. Place, grade, and shape stockpiles for proper drainage as approved by the Director's Representative.
- E. Excavation for Structures: Conform to elevations, lines, and limits indicated. Excavate to a vertical tolerance of plus or minus 1 inch. Extend excavation a sufficient lateral distance to provide clearance to execute the Work.
- F. Footings and Foundations: The foundation bearing grade will be established just prior to constructing the concrete foundations when concrete is to bear on undisturbed soil.
 - 1. Stepping Footings: Cut sloping surfaces under footings, foundations, steps, and where required for other Work as indicated.
 - 2. Pile Foundations: Stop excavations 6 to 12 inches above the bottom of pile cap elevation before the piles are placed. After pile installation, remove loose and displaced material and excavate to final grade, leaving a solid base to receive concrete pile caps.
 - 3. Where footings and other Work requiring similar soil support will rest entirely on rock, remove loose soil and loose rock and place concrete to the required elevations. Where footings and other Work requiring similar soil support will rest partially on rock and partially on soil, immediately notify the Director before any backfilling or concrete placement occurs; the Director will determine the correct foundation treatment for the Work.
- G. Slabs and Floors: Excavate to the following depths below bottom of concrete for addition of select granular material:
 - 1. Interior Floors: 6 inches unless otherwise indicated.
 - 2. Exterior Slabs and Steps: 12 inches unless otherwise indicated.

- H. Pipe Trenches: Open only enough trench length to facilitate laying pipe sections. Unless otherwise indicated on the Drawings, excavate trenches approximately 24 inches wide plus the outside pipe diameter, equally divided on each side of pipe centerline. Cut trenches to cross section, elevation, profile, line, and grade indicated. Accurately grade and shape trench bottom for uniform bearing of pipe in undisturbed earth. Excavate at bell and coupling joints to allow ample room for proper pipe connections.
 - 1. Trench in Rock: Excavate an additional 6 inches below bottom of pipe for bed of cushion material under the piping.
- I. Open Ditches: Cut ditches to cross sections and grades indicated.
- J. Pavement: Excavate to subgrade surface elevation.
- K. Unauthorized Excavations: Unless otherwise directed, backfill unauthorized excavation under footings, foundation bases, and retaining walls with compacted select granular material without altering the required footing elevation. Elsewhere, backfill and compact unauthorized excavation as specified for authorized excavation of the same classification, unless otherwise directed by the Director.
 - 1. Unauthorized excavations under structural Work such as footings, foundation bases, and retaining walls will be reported immediately to the Director before any concrete or backfilling Work commences.
- L. Notify the Director's Representative upon completion of excavation operations. Do not proceed with the Work until the excavation is inspected and approved. Inspection of the excavation by the Director's Representative will be made on three working days notice.
- M. Removal of Unsuitable Material Beneath Structures and Other Improvements: Excavate encountered unsuitable materials, which extend below required elevations, to additional depth as directed by the Director. Have cross sections taken, under the supervision of an independent Land Surveyor, to determine the quantity of such excavation. Do not backfill this excavation prior to quantity measurement.
 - 1. Such additional excavation and backfilling, not due to error, fault or neglect of the Contractor and exceeding the numeric quantities indicated on the Drawings, will be paid for at the unit prices specified in this Section.

3.05 DEWATERING

- A. Prior to the performance of any excavations provide dewatering methods such that the groundwater table is maintained at an elevation that is beneath the excavated depth.
- B. Prevent surface and subsurface water from flowing into excavations and trenches and from flooding the site and surrounding area.

- C. Do not allow water to accumulate in excavations or trenches. Remove water from all excavations immediately to prevent softening of foundation bottoms, undercutting footings, and soil changes detrimental to the stability of subgrades and foundations. Furnish and maintain pumps, sumps, suction and discharge piping systems, and other system components necessary to convey the water away from the Site.
- D. Convey water removed from excavations, and rain water, to collecting or run-off area. Cut and maintain temporary drainage ditches and provide other necessary diversions outside excavation limits for each structure. Do not use trench excavations as temporary drainage ditches.
- E. Provide temporary controls to restrict the velocity of discharged water as necessary to prevent erosion and siltation of receiving areas.

3.06 SETTLEMENT DETECTION

- A. Excavating beneath the bearing grades of an existing structure: Establish a settlement detection method approved by the Director's Representative for structures subject to settlement from excavation, sheeting or sheetpiling operations. Maintain surveillance to detect any settlement.
- B. Surcharging: Establish a settlement monitoring plan to accurately determine the settlements that have occurred and the rate that they occurred to adequately determine when settlement caused by surcharge is complete.

3.07 SHEETING, SHORING, AND BRACING

- A. Temporary Sheeting: Install temporary sheeting or sheetpiling with shoring and bracing as required to create a safe working environment and prevent settlement or other damage to adjacent grounds and structures resulting from excavation operations. Shore and brace sheeting in a manner which will not interfere with progress of other Work or related contracts (if any) on this project. Check shoring and bracing for settlement, and adjust for settlement. Promptly remove temporary sheeting, shoring, and bracing when no longer required.
- B. Permanent Sheeting: Install permanent steel sheetpiling where shown. Cut off top of permanent sheeting 12 inches below finish grade.

3.08 PLACING FILTER FABRIC

- A. Place and overlap filter fabric in accordance with the manufacturer's installation instructions, unless otherwise shown.
- B. Cover tears and other damaged areas with additional filter fabric layer extending three feet beyond the damage.
- C. Do not permit traffic or construction equipment directly on filter fabric.

- D. Backfill over filter fabric within two weeks after placement. Backfill in accordance with the fabric manufacturer's instructions and in a manner to prevent damage to the fabric.

3.09 PLACING FILL AND BACKFILL

- A. Surface Preparation of Fill Areas: Strip topsoil, remaining vegetation, and other deleterious materials prior to placement of fill. Remove all asphalt pavement in its entirety from areas requiring the placement of fill or break up old pavements to a maximum size of four inches. Prior to placement of fill, smooth out and compact areas where wheel rutting has occurred due to stripping or earthwork operations.
- B. Excavations: Backfill as promptly as Work permits, but not until completion of the following:
 - 1. Acceptance by the Director's Representative of construction below finish grade including, where applicable, dampproofing, waterproofing, perimeter insulation, and bearing capacity of supporting soil.
 - 2. Inspection, testing, approval, and recording locations of underground utilities.
 - 3. Removal of concrete formwork.
 - 4. Removal of temporary sheeting or sheetpiling and backfilling of voids caused by removals.
 - 5. Cutting off top of permanent sheeting or sheetpiling.
 - 6. Removal of trash and debris.
 - 7. Installation of permanent or temporary bracing on horizontally supported walls.
- C. Place backfill and fill materials in layers not more than eight inches thick in loose depth unless otherwise specified. Before compaction, moisten or aerate each layer as necessary to facilitate compaction to the required density. Do not place backfill or fill material on surfaces that are muddy, frozen, or covered with ice.
 - 1. Place fill and backfill against foundation walls, and in confined areas such as trenches not easily accessible by larger compaction equipment, in maximum six inch thick loose depth layers.
 - 2. For large fill areas, the layer thickness may be modified by the Director's Representative, at the Contractor's written request, if in the Director's Representative's judgment, the equipment used is capable of compacting the fill material in a greater layer thickness. This request will include the type and specifications of compaction equipment intended for use.
 - 3. For Open Graded Stone/Clean Stone (Item B-12, No. 1 crushed stone, No. 2 crushed stone, etc.) in excess of six inches: Material must be wrapped in separation fabric.
- D. Concrete walls:
 - 1. Do not place fill or backfill against concrete walls until the walls have attained 70 percent of their design strength. Place backfill against walls of structures containing basements or crawl spaces only after the first floor structural members are in place and any concrete components of the

first floor structural system have attained 70 percent of their concrete design strength.

2. Prevent wedging action of backfill against structures backfilled on both sides, by placing backfill uniformly around structure so that the elevation on each side never differs by more than 24 inches.

E. Foundation Drains:

1. Line pipe trench loosely with filter fabric. Lap successive sheets 18 inches.
2. Place underdrain filter material a minimum of 4 inches deep under pipe and 6 inches on both sides and over top of drain pipe.
3. Completely wrap underdrain filter material with filter fabric.
4. Within two weeks complete balance of backfill with selected fill extending 2 feet out from foundation wall and up to 6 inches below finished grade.

F. Perimeter Insulation: Before the insulation is installed, place and tamp specified backfill to a smooth plane even with the required elevation of the lower surface of the insulation.

G. Under Exterior Concrete Slabs and Steps:

1. Up to Subgrade Surface Elevation: Place selected fill when fill or backfill is required.
2. Subbase Material: Place 12 inches of select granular material over subgrade surface.

H. Under Interior Concrete Slabs:

1. Up to Subgrade Surface Elevation: Place selected fill when fill or backfill is required.
2. Subbase Material: Place six inches of select granular material over subgrade surface.

I. Under Pavements and Walks:

1. Up to Subgrade Surface Elevation: Place selected fill when fill or backfill is required.
2. Subbase Material: Place as indicated.

J. Landscaped Areas: Place suitable material when required to complete fill or backfill areas up to subgrade surface elevation. Do not use material containing rocks over four inches in diameter within the top 12 inches of suitable material.

K. Pipe Tunnels: Place selected fill a minimum of 12 inches on both sides and over top of tunnel.

L. Plastic Pipe in Trenches: Place cushion material a minimum of six inches deep under pipe, 12 inches on both sides, and 12 inches above top of pipe. Complete balance of backfill as specified.

1. Trench in Rock: Place a minimum six inch deep bed of cushion material under pipe.

- M. Copper Tubing and Steel Gas Pipe in Trenches: Place cushion material a minimum of six inches deep under pipe, 12 inches on both sides, and 12 inches above top of pipe. Complete balance of backfill as specified.
- N. Backfilling Excavation Resulting From Removal of Unsuitable Material Beneath Structures and Other Improvements: Backfill the excavation with compacted select granular material.
 - 1. Such additional backfilling, exceeding the numeric quantities indicated on the Drawings, is included in the unit prices specified in this Section.

3.10 ADDITIONAL REQUIREMENTS FOR PLACING FILL TO SUPPORT STRUCTURES

- A. Place fill within the entire area enclosed by a line ten feet outside the perimeter of the structure to be constructed as follows:
 - 1. Strip the area in accordance with the requirements for Surface Preparation of Fill Areas.
 - 2. Compact the stripped surface to 95 percent of maximum density.
 - 3. Place fill in horizontal layers not exceeding eight inches loose depth and compact layers as specified.
- B. Place fill within the entire area enclosed by a line 10 feet outside the perimeter of the structure to be constructed as follows:
 - 1. Strip the area in accordance with the requirements for Surface Preparation of Fill Areas.
 - 2. Proof roll the stripped surface with at least five passes of a vibratory drum compactor having a minimum unsprung drum weight of seven tons. Notify the Director's Representative of the proposed date for beginning proof rolling at least seven working days prior to commencing proof rolling.
 - 3. Excavate unsuitable materials (soft and unstable earth) disclosed by the proof rolling operation and replace with compacted Selected Fill material.
 - 4. Place fill in horizontal layers not exceeding eight inches loose depth and compact layers as specified.
- C. Obtain written approval of fill area compaction before excavating for footing.
- D. Excavate for footing width plus one foot on each side.
- E. Excavate one foot below footing elevations where bottom of footings are two feet or less above or four feet or less below original ground surface.
 - 1. Compact footing bottom and place a one foot bed of select granular material. Compact select granular material in six inch layers.
 - 2. Omit excavation and select granular material below bottom of footings where footing elevations are more than two feet above or more than 4 feet below original ground surface.

3.11 COMPACTION

- A. All materials with exception of open graded stone (No. 2 Crushed Stone, No. 1 Crushed Stone, Item B-12, etc.):
1. Compact each layer of fill and backfill for the following area classifications to the percentage of maximum density specified below and at a moisture content suitable to obtain the required densities, but at not less than three percent drier or more than two percent wetter than the optimum content as determined by ASTM D 698 (Standard Proctor) or 1557 (Modified Proctor).
 - a. Structures (entire area within ten feet outside perimeter): 95 percent.
 - b. Concrete Slabs and Steps: 95 percent.
 - c. Landscaped Areas: 90 percent.
 - d. Pavements and Walks: 95 percent.
 - e. Pipes and Tunnels: 95 percent.
 - f. Pipe Bedding: 95 percent.
 2. When the existing ground surface to be compacted has a density less than that specified for the particular area classification, break up and pulverize, and moisture condition to facilitate compaction to the required percentage of maximum density.
 3. Moisture Control:
 - a. Where fill or backfill must be moisture conditioned before compaction, uniformly apply water to the surface and to each layer of fill or backfill. Prevent ponding or other free water on surface subsequent to, and during compaction operations.
 - b. Remove and replace, or scarify and air dry, soil that is too wet to permit compaction to specified density. Soil that has been removed because it is too wet to permit compaction may be stockpiled or spread and allowed to dry. Assist drying by discing, harrowing or pulverizing, until moisture content is reduced to a value which will permit compaction to the percentage of maximum density specified.
 4. If a compacted layer fails to meet the specified percentage of maximum density, the layer will be recompacted and retested. If compaction cannot be achieved the material/layer will be removed and replaced. No additional material may be placed over a compacted layer until the specified density is achieved.
- B. Open graded Stone (Item B-12, No. 1 crushed stone, etc): Place material in maximum twelve inch lifts. Each lift shall be raked smooth and compacted through several passes of a walk behind vibratory roller. Compaction Testing is **not** required.

3.12 ROUGH GRADING

- A. Interior Grading: Trim unexcavated spaces within the building to levels indicated.
1. Subgrade for Interior Slabs: Compact as specified to receive fill material. Finish subgrade surface within 1 inch above or below level specified for fill required.

- B. Exterior Grading: Trim and grade area within the Grading Limit Line and excavations outside the limit line, required by this Contract, to a level of 4 inches below the finish grades indicated unless otherwise specified herein or where greater depths are indicated. Provide smooth uniform transition to adjacent areas.
 - 1. Slope cut and fill in transition areas, outside of the grading limit line, to meet corresponding levels of existing grades at a slope of 1 vertical to 2 horizontal unless otherwise indicated.
 - 2. Landscaped Areas: Provide uniform subgrade surface within 1 inch of required level to receive topsoil thickness specified. Compact fill as specified to within three inches of subgrade surface. Remove objectionable material detrimental to proper compaction or to placing full depth of topsoil. If the top three inches of subgrade has become compacted before placement of topsoil, harrow or otherwise loosen rough graded surface to receive topsoil to a depth of three inches immediately prior to placing topsoil.

3.13 SUBGRADE SURFACE FOR WALKS AND PAVEMENT

- A. Shape and grade subgrade surface as follows:
 - 1. Walks: Shape the surface of areas under walks to required line, grade and cross section, with the finish surface not more than 1 inch above or below the required subgrade surface elevation.
 - 2. Pavements: Shape the surface of areas under pavement to required line, grade and cross section, with the finish surface not more than 1/2 inch above or below the required subgrade surface elevation.
- B. Grade Control: During construction, maintain lines and grades including crown and cross-slope of subbase course.
- C. Thoroughly compact subgrade surface for walks and pavement by mechanical rolling, tamping, or with vibratory equipment as approved to the density specified.
- D. Shoulders: Place shoulders along edges of filled subgrades to prevent lateral movement. Construct shoulders of selected fill material, placed in such quantity to compact to thickness of each subgrade course layer. Compact and roll at least a 2'-0" wide additional layer of each subgrade course.

3.14 FINISH GRADING

- A. Uniformly grade rough graded areas within limits of the Grading Limit Line to finish grade elevations indicated.
- B. Grade and compact to smooth finished surface within tolerances specified, and to uniform levels or slopes between points where finish elevations are indicated or between such points and existing finished grade.

- C. Grade areas adjacent to building lines so as to drain away from structures and to prevent ponding.
- D. Finish surfaces free from irregular surface changes, and as follows:
 - 1. Grassed Areas: Finish areas to receive topsoil to within one inch above or below the required subgrade surface elevations.
 - 2. Walks: Place and compact subbase material as specified. Shape surface of areas under walks to required line, grade and cross section, with the finish surface not more than 1/2 inch above or below the required subbase elevation.
 - 3. Pavements: Place and compact subbase material as specified. Shape surface of areas under pavement to required line, grade and cross section, with the finish surface not more than 1/2 inch above or below the required subbase elevation.
 - 4. Building Slabs: Grade subbase material smooth and even, free of voids, compacted as specified, and to required subbase elevation. Finish final grades within a tolerance of 1/4 inch when tested with a ten foot straightedge.
 - 5. Surfaces To Receive Vapor Barrier: Provide smooth surfaces graded, tamped and/or rolled, entirely free of obstructions or protruding objects.
- E. Spread topsoil directly upon prepared subgrade surface to a depth measuring FOUR inches after natural settlement of the topsoil has occurred in areas to be seeded or to receive sod. Place to greater depth when necessary to adjust grades to required elevations.
 - 1. Approved existing topsoil within the Grading Limit Line may be used. Provide additional topsoil from outside sources as required.
- F. Finish topsoil surface free of depressions which will trap water, free of stones over 1 inch in any dimension, and free of debris.

3.15 MAINTENANCE AND RESTORATION

- A. Restore grades to indicated levels where settlement or damage due to performance of the Work has occurred. Correct conditions contributing to settlement. Remove and replace improperly placed or poorly compacted fill materials.
- B. Restore pavements, walks, curbs, lawns, and other exterior surfaces damaged during performance of the Work to match the appearance and performance of existing corresponding surfaces as closely as practicable.
- C. Topsoil and seed or sod damaged lawn areas outside the GLL and new lawn areas inside the GLL. Water as required until physical completion of the Work.

3.16 DISPOSAL OF EXCESS AND UNSUITABLE MATERIALS

- A. Remove from State property and dispose of excess and unsuitable materials, including materials resulting from clearing and grubbing and removal of existing improvements.

- B. Transport excess and unsuitable materials, including materials resulting from clearing and grubbing and removal of existing improvements, to spoil areas on State property designated by the Director's Representative, and dispose of such materials as directed.
- C. Transport excess topsoil to areas on State property designated by the Director's Representative. Smooth grade deposited topsoil.

3.17 FIELD QUALITY CONTROL

- A. Compaction Testing: Notify the Director's Representative at least three working days in advance of all phases of filling and backfilling operations. Compaction testing will be performed by the Director's Representative to ascertain the compacted density of the fill and backfill materials. Compaction testing will be performed on certain layers of the fill and backfill as determined by the Director's Representative. If a compacted layer fails to meet the specified percentage of maximum density, the layer will be recompact and will be retested. No additional material may be placed over a compacted layer until the specified density is achieved.

3.18 PROTECTION

- A. Protect graded areas from traffic and erosion, and keep them free of trash and debris.

END OF SECTION